

## Site Roads and Pitches Dunbar Camping & Caravanning Club



Subbase and timber edgings to site roads.



Tarmac to site road and completed pitches



Site Manager Pitch with timber fencing



Large MPH JCB excavator required on existing hard ground

Client: Camping & Caravanning Club	Value: £170,000
Location: Dunbar, Edinburgh	Duration: 6 weeks

### **Project information**

This project was the Re-surfacing of existing site roads and Hardstanding's at The Camping & Caravanning Club site at Dunbar, near Edinburgh.

The works comprised the following:

- Plane off the existing stone from the roads and replace with tarmac to the site roads.
- Excavate and scrape the existing pitches and hardstanding's and re-surface with angular stone, stockpile un-used stone on site for future use.
- Install timber edgings to all existing site roads.
- Construct a new staff pitch for the site manager including timber fencing.
- Drainage works throughout the site.
- Ducting works and installation of cabling for services.
- Construct new speed bumps throughout the site.
- Lay new turf and grass seeding to disturbed areas.

The works were undertaken in the winter months of 2015/2016, and successfully completed for the Opening of the Easter Season in late March 2016.